



MARQUEE INSTALLATION HANDBOOK

Porches & Entrancesways



Solent Canopy Assembly Instructions

- Equipment needed -
 - Solent canopy sheet
 - Push up masts 2 off
 - Ratchet straps 2 off
 - Steel stakes 2 off

- Erect frame in standard manner.
- Mark out location for base of masts
- Mark out and stake ratchet points
- Lay Solent canopy to one side of frame and throw over pulling rope.
- Attach throw over rope to D ring and feed canopy in to top Kader track at eave level.
- Pull over until centre of canopy at ridge.
- Feed sides of canopy into kader channel of legs and tension to base plate
- Attach webbing straps to tensioning d rings
- Push centre pin of masts through peaks and stand up in base locations
- Ratchet up tension straps until taut.

Dismantling:

- Loosen tension from ratchets
- Remove masts
- Pull kader out of legs
- Pull roof sheet back to one side
- Fold and pack away clean & dry.

9m/12m Porch Installation Instructions

Tools needed

- ❑ 17 & 19mm diameter spanners
- ❑ Low step ladder/step up

Process

Frame

- ❑ Construct 9m or 12m frame as usual.
- ❑ In porch bay, remove standard eave rail. Using steps, lift the porch eave section into position and bolt to roof beams. NOTE: There are 4 holes available on the eave section to be used for either the 9m or 12m roof beams. 2 each of the specific bolts are supplied to attach to either size.



- ❑ Attach the two porch roof beams and bolt onto the porch eave rail section.
- ❑ Fit standard purlin and eave purlin to porch roof beams.

PVC

- ❑ The tent roof should secure with bungees to the eave as usual.
- ❑ Insert porch roof into kade tracks working towards the main tent. NOTE: Pulling evenly will prevent snagging in the tracks.
- ❑ Secure the side-release straps around the tent eave and tighten the porch roof with the bungees onto the exterior eave (as with a standard roof).
- ❑ Secure the toggles on the porch roof to the bungees on the tent roof.